

BRAHMAPUTRA VALLEY FERTILIZER CORPORATION LIMITED, NAMRUP

CIVIL ENGINEERING DEPARTMENT

**Name of work : Mastic flooring in LPG Gas Godown at BVFCL.**

BILL OF QUANTITY / SCHEDULE OF RATES

| Sl.No. | Item Description  | Unit | Rate | Qty | Amount |
|--------|---|------|------|-----|--------|
| 1      | Providing and laying bitumen mastic wearing course (as per specifications) with industrial bitumen of grade 85/25 conforming to IS : 702, prepared by using mastic cooker and laid to required level and slope, including providing antiskid surface with bitumen precoated fine grained hard stone chipping of approved size at the rate of 0.005 cum per 10 sqm and at approximate spacing of 10 cm centre to centre in both directions, pressed into surface protruding 1 mm to 4mm over mastic surface, including cleaning the surface, removal of debris etc. all complete. (Considering bitumen using 10.2% as per MORTH specification).40 mm thick | Sqm  |      | 82  |        |
|        | Total Excluding GST   |      |      |     |        |